

CHEMTOPS

INSTALLATION PROCESS

Installation Process

Arrival

Our team uses specialized tools and equipment, according to the requirements of each job. The furniture will then be placed in the areas as specified by the approved drawings of the job.

Upon placement, it shall be unpacked and inspected for quality assurance.

Leveling Cabinets & Specialized Tooling

We use a specialized process to level off the cabinets and countertops.

We use a two part epoxy seaming agent to seem all tops and back splashes to tops where necessary.

Next our team will complete an inspection of:

- **Door Slides**
- **Door Hinges**
- **Door Alignment**
- **Cabinets**
- **Countertops**

Completion

Upon inspection, by the general contractor of the end user, we will have them complete a short survey and the job is then declared complete.



THIS PAGE WAS LEFT BLANK INTENTIONALLY